

## **LDEQ Inspections**

#### **Small MS4 Inspections**





#### What you need:

- NOI
- Permit
- Storm Water Management Plan
- Annual Reports
- Monitoring Records
- Map of storm water outfalls





# Has your Storm Water Management Program been developed, implemented, and enforced within five years of initial authorization?





The Storm Water Management Program shall be described in a detailed written Storm Water Management Plan. The SWMP shall be designed to reduce the discharge of pollutants from your small MS4 to the Maximum Extent Possible (MEP) to protect water quality and satisfy the appropriate water quality requirements of the Louisiana Environmental Quality Act.





#### The LDEQ inspector will review:

- Storm water control measures
- Best Management Practices
- The measurable goals of each
- How these are implemented
- Who is responsible for implementation





## Six minimum control measures should be included in your SWMP:

- 1) Public education and Outreach on Storm Water Impacts
- 2) Public Involvement/Participation
- 3) Illicit Discharge Detection and Elimination
- 4) Construction Site Storm Water Runoff Control
- 5) Post-Construction Storm Water Management in New Development and Redevelopment
- 6) Pollution Prevention/Good House Keeping for Municipal Operations





#### The SWMP should be reviewed annually.

## Annual Reports must be submitted to LDEQ by March 10 each year for the preceding calendar year.





#### **Monitoring Records**

- Dry weather screening
- Sampling records if applicable
- Constructions Site Inspection Records





If your MS4 discharges to a receiving water on the 303 d list of the Biennial Report of Impaired waters and your discharges contain one of the pollutants for which the waterbody is impaired, then you must document in your SWMP how the BMPs and other controls will reduce the discharge of pollutants of concern. If a TMDL has been approved for the waterbody, you must describe how your SWMP is consistent with any TMDL requirements applicable to your discharge. If no TMDL is approved, you must describe how your BMPs and other controls will reduce the pollutant from your discharge.





If a Waste Load Allocation has been assigned to discharges of a particular pollutant from your MS4 to a particular subsegment, then you must describe and implement a sampling and analysis program to determine whether the storm water controls you have implemented are adequate to meet the WLA.





#### 2010 Biennial Report http://www.deq.louisiana.gov/portal/tabid/98/Default.aspx

Subsegment 060212 Chatlin Lake Canal

- FWP IRC4a Nitrate/Nitrite
- FWP IRC4a Dissolved Oxygen
- FWP IRC4a Total Phosphorus
- FWP IRC4a Sedimentation/Siltation
- FWP IRC4a Total Suspended Solids
- FWP IRC4a Turbidity
- FWP IRC 5 Total Dissolved Solids

Discharges from MS4 Discharges from MS4 Discharges from MS4 Agriculture and Sources Unknown Agriculture and Sources Unknown Agriculture and Sources Unknown ewage discharges from

unsewered areas, agriculture, and rural residences





#### **Storm Water Construction Activity Inspections**

#### LAR100000 - Five acres or more

#### LAR200000 - One - Five acres





## A posted notice shall be placed near the entrance with the following information:

- LPDES permit number
- name and phone number of a contact person
- a brief description of the project
- the SWPPP or location thereof





#### **Contents of a Storm Water Pollution Prevention Plan**

Site Description Controls Maintenance Inspections Non-storm water discharges Contractor & Subcontractor Responsibilities Signed certification statement





#### Site Inspection

- Size of the disturbed area
- Storm water control measures are installed properly
- Erosion and sediment gone off-site
- Off-site tracking
- Signs of oil staining
- Examine receiving ditch or stream



### **CASE STUDY**



#### Double 00 Construction Company Ouachita Parish , La

September 7, 2006 and October 25, 2006



### 9-7-06



Improper silt fence maintenance resulted in soil leaving the construction site into the street at both entrances, the road ditch, and a dry slough bed in a publicly owned nature park. The project manager could not produce a SWPPP or a storm water discharge permit. He was unsure if such documents existed. Subsequent phone calls could not confirm if the company had a SWPPP or permit.





#### 10-25-06

Off –site tracking of mud was observed in the street at both entrances to the construction site. Muddy water was observed in the road ditch. In two areas, silt fence was improperly installed with gaps at the base that allowed sediment to discharge into the road ditch during a rainstorm.











LOUISIANA















































### CONTACT INFORMATION

john.posey@la.gov

#### **Office of Environmental Compliance**

#### Phone: 318-362-5438

